BRUHATH BANGALORE MAHANAGARA PALIKE,

Office of the Executive Engineer Dasarahalli Division,

Schedule-B

NAME OF WORK: Desilting of drains and removal of debries and providing covering slab for Dasarahalli

Sl. No	Description of work	Unit	Qty	Rate quoted by the Contractor MUNIRAJA NAIK	
				In Figures (Rs.)	Amount
1	2	3	4	5	7
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications	Cum	1440	182.0	262080
2	Removing & Refixing stone slabs of drains and pointing	Sqm	3600	97.0	349200
3	Providing and fixing precast RCC slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including from work lift charges, curing and concrete finished surface on both side etc.,	Sqm	624.6	1421.0	887556.6

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engine
Dasarahalli Divisi
BBM